T.G.E. PROS

Professional Electrical Services

Texas Master Electrician License #750779

tgebilling@gmail.com | electrapro.app

PROJECT FOLLOW-UP MEMO & ESTIMATE

Date:	February 19, 2026
Client:	Eleanor Williams
Project:	2200 Willowick Rd, Apt. 9 H - Full Remodel
Prepared By:	Chris - T.G.E. PROS

PROJECT SUMMARY

Full apartment remodel at 2200 Willowick Rd, Apt. 9 H for Eleanor Williams. The project involves complete electrical upgrades across four areas: Office & Hallway, Master Bedroom, Master Bathroom, and Guest Bathroom. Work includes LED conversions, new can light installations, circuit extensions for electric toilet, sconce installations, and switch box upgrades. T.G.E. PROS is providing all electrical services. Willer and team are handling general contracting including demolition, plumbing, structural work, sheetrock, painting, countertop/cabinet installation, tile work, and balcony resurfacing.

SCOPE OF ELECTRICAL WORK

Office & Hallway: Remove and inspect all receptacles, load test and replace if damaged. Retrofit 6 can lights to LED fixture kits with driver compatibility verification. Delete preexisting phone line. Convert 6 ft of kitchen lighting bars to LED-capable fixtures with new LED lamps. Verify neutral wire presence at all switch locations.

Master Bedroom: Remove and inspect all receptacles, load test and replace if damaged. Delete preexisting phone line. Install 4 new can lighting fixtures in ceiling with proper IC-rated housing. Convert 2-gang switch box to 3-gang switch box with 3rd switch to control added 6 inch can lights. Run new circuit wiring through existing wall cavities.

Master Bathroom: Replace 2 closet lighting fixtures with LED. Install 4 new LED can lighting fixtures in customer desired locations. Convert 3 existing can lighting fixtures to LED. Install sconce lighting fixtures in customer desired locations. Convert single-gang switch to 2-gang switch (ceiling lights + sconces). Extend bathroom circuit to required location for new electric toilet with dedicated 20A GFCI-protected circuit. Verify proper grounding and bonding for wet location.

Guest Bathroom: Convert 3 existing can lighting fixtures to LED. Install sconce lighting fixtures in customer desired locations. Convert single-gang switch to 2-gang switch (ceiling lights + sconces). Install 2 new can lighting fixtures in bathroom ceiling with IC-rated housing.

GFCI Compliance Upgrades: Install and upgrade GFCI protection in both bathrooms and kitchen per NEC 2023 requirements. Test all existing GFCI devices. Replace non-compliant receptacles in wet locations. Verify arc-fault protection where required by code.

Panel Load Assessment and Breaker Upgrades: Perform full panel load calculation to verify capacity for added circuits (electric toilet, new lighting loads). Replace any worn or undersized breakers. Label all new circuits. Provide load calculation documentation for permit inspection.

GENERAL CONTRACTOR SCOPE (WILLER & TEAM)

Demolition of both bathrooms, wallpaper removal, kitchen tile demo, balcony tile demo, and all pre-discussed demolitions. Debris removal to building-designated location.

All plumbing and structural additions including converting hallway closet into guest bathroom extension. Metal studs required per building code. Copper plumbing required per building code.

Sheetrock for new walls and patch work. Texture and painting per client specifications. Installation of countertops, sinks, faucets, and premade cabinets. Tile installation with cement and grout in both bathrooms and kitchen backsplash. Balcony prep and surface material installation.

GC Labor: $21,650 (does not include materials)
Building-required ventilation: 3 setups at $325 each = $975

ADDITIONAL TRADES REQUIRED (NOT YET PRICED)

The following subcontractors need to be sourced and quoted:

1. A/C Technician - Duct servicing or replacement
2. Hardwood Floor Crew - Bedroom flooring installation
3. Wallpaper Installer - New wallpaper installation (Willer demos existing, does not install new)
4. Custom Woodwork Crew - Added custom woodwork per client design

These trades should provide separate bids. COI and license verification required before work begins.

INSURANCE & COMPLIANCE REQUIREMENTS

Before starting work, verify the following:

- General Liability Insurance: $1M per occurrence / $2M aggregate minimum
- Workers Compensation: Required for all employees on site
- Certificate of Insurance (COI): Must be submitted to building management
- Building may require T.G.E. PROS and all subcontractors to be named as Additional Insured
- All subcontractors must provide their own COI before entering the building
- Building ventilation requirements must be met ($975 budgeted for 3 setups)
- Electrical permit: $1,000 budgeted - pull before work begins

- Request building access hours and noise restriction schedule

RECOMMENDED PAYMENT SCHEDULE

Milestone-based payment structure for the electrical scope:

Deposit (before work begins): 30% = $7,354
After rough-in completion and inspection: 40% = $9,805
After final trim-out and inspection: 30% = $7,353

Total: $24,512

Note: Materials ($8,112) should be purchased before each phase. Confirm with client whether materials are paid upfront or included in milestone payments.

IMPORTANT EXCLUSIONS & CLARIFICATIONS

The following items are NOT included in the T.G.E. PROS electrical estimate:

1. Sheetrock repair after electrical cuts - coordinate with Willer or quote separately
2. Any additional circuits or outlets discovered during demo not in original scope
3. Panel upgrades if existing panel cannot support the new load
4. Low voltage / data wiring unless added to scope
5. Appliance hookups beyond the electric toilet circuit

Change orders will be documented and approved by the client before any additional work.

ELECTRICAL ESTIMATE BREAKDOWN

Area / Scope	Time	Materials	Labor
Office & Hallway	9 hrs	$430	$900
Master Bedroom	13 hrs	$565	$1,350
Master Bathroom	25 hrs	$1,525	$2,750
Guest Bathroom	17 hrs	$995	$1,900
GFCI Compliance Upgrades	4 hrs	$285	$450
Panel Load Assessment & Breakers	3.5 hrs	$312	$500

Total Materials:	$8,112
Total Labor:	$15,400
Permitting:	$1,000
PROJECT TOTAL:	**$24,512**

CLIENT DISCUSSION QUESTIONS

For Chris to review with Eleanor Williams

1. What are the building approved work hours and any noise restrictions? Some condos only allow work between 9am-5pm weekdays.
2. Can we get the building engineer contact information? We will need to coordinate debris removal to their designated location.
3. Has the building management provided their specific insurance requirements? Do they require Additional Insured endorsement, Primary and Non-Contributory, or Waiver of Subrogation on our policy?
4. For the electric toilet in the master bathroom - has the specific model been selected? We need the electrical specifications (voltage, amperage) to size the circuit correctly.
5. What is the client preference for can light color temperature? Warm white (2700K), neutral (3000K), or daylight (4000K)? This affects all 13+ new LED fixtures.
6. Has the client finalized the sconce fixture selections for both bathrooms? We need these in hand or ordered before rough-in for correct junction box placement.
7. Is the existing electrical panel adequate for the additional circuits? If not, a panel upgrade should be discussed and quoted before we start.
8. Who is responsible for the sheetrock repair after our electrical cuts? This is excluded from our estimate and needs to be assigned to Willer or quoted separately.
9. What is the project timeline and sequencing with Willer crew? We need walls open for rough-in before drywall, then return for trim-out after painting.
10. Are there any other electrical needs being considered? (EV charger, smart home systems, USB outlets, under-cabinet lighting, etc.) Better to include now.
11. Does the client want dimmer switches for any of the new lighting circuits? This needs to be specified before we purchase switches.
12. Will the 3 ventilation setups ($975) be shared among all trades or does each contractor need their own?
13. Has the building approved our scope of work? Some condo associations require architectural review board approval before electrical modifications.
14. What is the client preferred payment method - check, bank transfer, credit card, or PayPal? Is the milestone payment schedule (30/40/30) acceptable?

Additional Notes

This is a multi-trade coordination project requiring careful scheduling. Recommend holding a pre-construction meeting with Willer, Eleanor, and all subcontractors to establish the project timeline and communication protocol. Total estimated project cost across all trades is $55,000 - $75,000+. Our electrical portion represents approximately 30-35% of the overall project.

This document is confidential and intended for client discussion purposes.